



November 18, 2019

City of Round Rock
Attn: Eddie Zepata
2008 Enterprise Dr
Round Rock, Texas

Bid Proposal: Basin 2 & 3, Cycle 3-Wastewater PB
Round Rock, Texas
Pipe Bursting Replacement

BuyBoard Contract # 555-18

Dear Bidder,

PM Construction is pleased to offer the following proposal pricing to provide pipe bursting (PB) replacement services of the 8-Inch sanitary sewer lines for the above referenced project. Our proposal is based on the documents provided by City of Round Rock. This pricing includes providing all labor, material, supervision, and equipment necessary to complete the scope of work as listed below.

Scope of work performed by PM Construction:

- Provide pre-work submittals.
- PM Construction will perform pre-rehab CCTV & cleaning (normal only). Two-wheel drive vehicle access to manholes is required for this work.
- PB replacement to utilize DR 19 HDPE for replacement pipe, utilizing pneumatic bursting methods only. All excavations will be backfilled with previously excavated material.
- Reinstatement of service laterals to PB mains will be made utilizing saddles with stainless steel bands and reconnecting to the existing lateral.
- Pricing is based on completing diameters & associated quantities as listed in this proposal's schedule of values. Any change in overall or segmental length, host pipe diameters, host pipe material, replacement material or thickness could result in pricing changes.
- Demobilize all construction equipment and clean-up of all identifiable debris generated by PM Construction crew(s).

IPR SC proposes to complete the above scope of services for the prices listed below:

Item No.	Description	Qty	Unit	Unit Price	Total
P13	Travel and Mobilization- TML Region 13 (Austin)	6	EA	\$ 6,000.00	\$ 36,000.00
4902	FOREMAN - REGULAR (Pre-Site Inspection)	67	HR	\$ 30.00	\$ 2,010.00
4911	Barricades, Signs, and Traffic Handling (per setup)	1	EA	\$ 3,500.00	\$ 3,500.00
4915	SWPPP	1	EA	\$ 2,500.00	\$ 2,500.00
204	Burst existing 6" or 8" to 8" IPS SDR 19 (0'- 8' deep)	3,210	LF	\$ 55.00	\$ 176,550.00
205	Burst existing 6" or 8" to 8" IPS SDR 19 (8'- 12' deep)	11,930	LF	\$ 60.00	\$ 715,800.00
401	Sewer Main Television Inspection (8" through 15" Diameter)	15,140	LF	\$ 4.00	\$ 60,560.00
409	Sewer Main Cleaning - Normal (8" through 15" Diameter)	15,141	LF	\$ 4.00	\$ 60,564.00
451	6" - 12" Post TV Inspection After Rehabilitation	15,142	LF	\$ 5.00	\$ 75,710.00
1201	External reconnect (0'- 8' deep) up to 5 linear feet	125	EA	\$ 920.00	\$ 115,000.00
1206	Extra length service connection over 5 linear feet	1,100	LF	\$ 40.00	\$ 44,000.00
1207	Remove and replace or install cleanout	125	EA	\$ 1,850.00	\$ 231,250.00
1207D	DISCOUNT Item #1207- Remove and replace or install cleanout	125	EA	\$ (686.75)	\$ (85,843.75)
1711	Repair/Rehab wooden fence with new	150	LF	\$ 36.80	\$ 5,520.00
					\$1,443,120.25

This pricing does **not** include the cost for the following:

- Prevailing wages.
- Heavy pipe cleaning, including but not limited to grease, roots, tuberculation removal, mechanical cleaning, debris disposal, dump site, etc.
- Dewatering, grouting, vibration monitoring, point repairs (internal or open cut), new installation, etc. to be handled by Others if required.
- Bypass pumping outside of (1) 4" trash pump & 500' of lay flat discharge hose.
- Testing of any kind.
- Changes in pipe diameter, quantities, host pipe material, replacement pipe material, or lengths (overall or segmental), curing or bursting methods will result in pricing changes. Static bursting is NOT included in this proposal. Bursting cast iron (CI) or ductile iron (DI) mains is NOT included in this proposal.
- Locating of buried manholes or Owner right of way by Others (if required).
- Haul off of unsuitable excavated materials or suitable replacement material hauled in.
- Rock excavation or blasting.
- Any work not specifically detailed in this proposal.
- Pricing firm for 30 days from date of this proposal.

Thank you for the opportunity to offer you this proposal. Should you have any questions or require additional information, please do not hesitate to contact me.

Sincerely,
PM Construction
 Collis Parish / Justin Mouton
 Business Development