

THE CITY OF ROUND ROCK
Transportation Department
 3400 Sunrise Road
 Round Rock, Texas 78665



Steven Esche
 5/8/2025


BIDS EXTENDED AND CHECKED
RESPONSES: 2
CHECKED BY: Aguirre & Fields
DATE: 5/8/2025

CERTIFIED BID TABULATION

LOWEST BID

CONTRACT: South Mays Street Wall Stabilization Project				Aaron Concrete Contractors		Austin Filter Systems	
LOCATION: Round Rock TX				Statement of Safety? Yes		Statement of Safety? Yes	
DATE: May 08, 2025				Addendum(s) 1		Addendum(s) 1	
				Bid Bond? Yes		Bid Bond? Yes	
ITEM #	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE	COST	UNIT PRICE	COST
1	100 6002 PREPARING ROW	2.00	STA	\$10,000.00	\$20,000.00	\$20,000.00	\$40,000.00
2	104 6014 REMOVING CONC (FOUNDATIONS)	18.00	CY	\$250.00	\$4,500.00	\$300.00	\$5,400.00
3	104 6015 REMOVING CONC (SIDEWALKS)	78.00	SY	\$50.00	\$3,900.00	\$25.00	\$1,950.00
4	104 6034 REMOVING CONC (COPING)	145.00	LF	\$50.00	\$7,250.00	\$100.00	\$14,500.00
5	104 6037 REMOVE CONC (RAIL)	290.00	LF	\$50.00	\$14,500.00	\$50.00	\$14,500.00
6	104 6049 REMOVE CONCRETE (MSE PANELS)	581.00	SF	\$50.00	\$29,050.00	\$60.00	\$34,860.00
7	105 6075 REMOV STAB BASE AND ASPH PAV (10'-18")	445.00	SY	\$50.00	\$22,250.00	\$50.00	\$22,250.00
8	110 6001 EXCAVATION (ROADWAY)	611.00	CY	\$35.00	\$21,385.00	\$30.00	\$18,330.00
9	110 6003 EXCAVATION (SPECIAL)	594.00	CY	\$50.00	\$29,700.00	\$25.00	\$14,850.00
10	132 6001 EMBANKMENT (FINAL)(ORD COMP)(TY A)	594.00	CY	\$64.00	\$38,016.00	\$60.00	\$35,640.00
11	132 6005 EMBANKMENT (FINAL)(ORD COMP)(TY C)	211.00	CY	\$210.00	\$44,310.00	\$20.00	\$4,220.00
12	160 6003 FURNISHING AND PLACING TOPSOIL (4")	2,336.00	SY	\$8.00	\$18,688.00	\$5.00	\$11,680.00
13	164 6007 BROADCAST SEED (PERM) (URBAN) (CLAY)	2,336.00	SY	\$0.36	\$840.96	\$0.50	\$1,168.00
14	164 6009 BROADCAST SEED (TEMP) (WARM)	1,168.00	SY	\$0.26	\$303.68	\$0.20	\$233.60
15	164 6011 BROADCAST SEED (TEMP) (COOL)	1,168.00	SY	\$0.29	\$338.72	\$0.20	\$233.60
16	168 6001 VEGETATIVE WATERING	348.00	MG	\$43.00	\$14,964.00	\$30.00	\$10,440.00
17	169 6001 SOIL RETENTION BLANKETS (CL 1) (TY A)	2,336.00	SY	\$2.00	\$4,672.00	\$4.00	\$9,344.00
18	247 6231 FL BS (CMP IN PLACE)(TY A GR 1-2)(10")	444.00	SY	\$67.00	\$29,748.00	\$35.00	\$15,540.00
19	310 6005 PRIME COAT (AE-P)	89.00	GAL	\$12.00	\$1,068.00	\$5.00	\$445.00
20	400 6001 STRUCT EXCAV	31.00	CY	\$1,047.00	\$32,457.00	\$50.00	\$1,550.00
21	400 6005 CEM STABIL BKFL	20.00	CY	\$605.00	\$12,100.00	\$300.00	\$6,000.00
22	403 6001 TEMPORARY SPL SHORING	790.00	SF	\$129.00	\$101,910.00	\$100.00	\$79,000.00
23	410 6001 SOIL NAIL ANCHOR	840.00	LF	\$150.00	\$126,000.00	\$110.00	\$92,400.00
24	416 6001 DRILL SHAFT (18 IN)	540.00	LF	\$233.00	\$125,820.00	\$350.00	\$189,000.00
25	420 6043 CL C CONC (FOOTING)	121.00	CY	\$1,879.00	\$227,359.00	\$1,000.00	\$121,000.00
26	420 6074 CL C CONC (MISC)	9.00	CY	\$2,857.00	\$25,713.00	\$1,600.00	\$14,400.00
27	422 6015 APPROACH SLAB	51.00	CY	\$1,138.00	\$58,038.00	\$800.00	\$40,800.00
28	423 6015 RETAINING WALL (SPECIAL)	839.00	SF	\$110.00	\$92,290.00	\$185.00	\$155,215.00
29	427 6002 CONCRETE PAINT FINISH	32,400.00	SF	\$2.00	\$64,800.00	\$0.32	\$10,368.00
30	429 6007 CONC STR REPAIR (VERTICAL & OVERHEAD)	105.00	SF	\$230.00	\$24,150.00	\$385.00	\$40,425.00
31	432 6041 RIPRAP (SPECIAL)	48.00	CY	\$1,329.00	\$63,792.00	\$700.00	\$33,600.00
32	438 6006 CLEANING AND SEALING JOINTS (CL 3)	102.00	LF	\$20.00	\$2,040.00	\$55.00	\$5,610.00
33	450 6004 RAIL (TY T221)	145.00	LF	\$311.00	\$45,095.00	\$250.00	\$36,250.00
34	450 6036 RAIL (TY C411)	145.00	LF	\$627.00	\$90,915.00	\$800.00	\$116,000.00
35	500 6001 MOBILIZATION	1.00	LS	\$200,000.00	\$200,000.00	\$250,000.00	\$250,000.00
36	502 6001 BARRICADES, SIGNS AND TRAFFIC HANDLING	9.00	MO	\$1,724.00	\$15,516.00	\$2,000.00	\$18,000.00
37	506 6020 CONSTRUCTION EXITS (INSTALL)(TY 1)	200.00	SY	\$43.00	\$8,600.00	\$40.00	\$8,000.00
38	506 6024 CONSTRUCTION EXITS (REMOVE)	200.00	SY	\$33.00	\$6,600.00	\$15.00	\$3,000.00
39	506 6038 TEMP SEDMT CONT FENCE (INSTALL)	1,063.00	LF	\$5.00	\$5,315.00	\$10.00	\$10,630.00
40	506 6039 TEMP SEDMT CONT FENCE (REMOVE)	1,063.00	LF	\$1.00	\$1,063.00	\$3.00	\$3,189.00
41	506 6040 BIODEG EROSN CONT LOGS (INSTL) (8")	331.00	LF	\$5.00	\$1,655.00	\$10.00	\$3,310.00
42	506 6043 BIODEG EROSN CONT LOGS (REMOVE)	331.00	LF	\$1.00	\$331.00	\$3.00	\$993.00
43	512 6009 PORT CTB (FUR & INST)(LOW PROF)(TY 1)	460.00	LF	\$27.00	\$12,420.00	\$100.00	\$46,000.00
44	512 6010 PORT CTB (FUR & INST)(LOW PROF)(TY 2)	40.00	LF	\$9.00	\$360.00	\$100.00	\$4,000.00
45	512 6033 PORT CTB (MOVE)(LOW PROF)(TY 1)	420.00	LF	\$10.00	\$4,200.00	\$15.00	\$6,300.00
46	512 6034 PORT CTB (MOVE)(LOW PROF)(TY 2)	40.00	LF	\$10.00	\$400.00	\$15.00	\$600.00
47	512 6057 PORT CTB (REMOVE)(LOW PROF)(TY 1)	460.00	LF	\$27.00	\$12,420.00	\$15.00	\$6,900.00
48	512 6058 PORT CTB (REMOVE)(LOW PROF)(TY 2)	40.00	LF	\$9.00	\$360.00	\$15.00	\$600.00
49	531 6002 CONC SIDEWALKS (5")	79.00	SY	\$159.00	\$12,561.00	\$100.00	\$7,900.00
50	628 6001 RELOCATE ELECTRICAL SERVICES	4.00	EA	\$6,012.00	\$24,048.00	\$12,500.00	\$50,000.00
51	662 6064 WK ZN PAV MRK REMOV (W)6"(BRK)	187.00	LF	\$2.00	\$374.00	\$50.00	\$9,350.00
52	662 6067 WK ZN PAV MRK REMOV (W)6"(SLD)	2,543.00	LF	\$2.00	\$5,086.00	\$10.00	\$25,430.00
53	662 6098 WK ZN PAV MRK REMOV (Y)6"(SLD)	7,051.00	LF	\$2.00	\$14,102.00	\$5.00	\$35,255.00
54	666 6225 PAVEMENT SEALER 6"	2,936.00	LF	\$1.00	\$2,936.00	\$0.50	\$1,468.00
55	666 6306 RE PM W/RET REQ TY 1 (W)6"(BRK)(100MIL)	587.00	LF	\$2.00	\$1,174.00	\$1.00	\$587.00
56	666 6321 RE PM W/RET REQ TY 1 (Y)6"(SLD)(100MIL)	2,349.00	LF	\$2.00	\$4,698.00	\$1.00	\$2,349.00
57	672 6009 REFL PAV MRKR TY II-A-A	32.00	EA	\$13.00	\$416.00	\$10.00	\$320.00
58	672 6010 REFL PAV MRKR TY II-C-R	32.00	EA	\$13.00	\$416.00	\$25.00	\$800.00
59	677 6002 ELIM EXT PAV MRK & MRKS (6")	3,158.00	LF	\$6.00	\$18,948.00	\$1.00	\$3,158.00
60	752 6022 TREE TRIMMING AND BRUSH REMOVAL	200.00	LF	\$143.00	\$28,600.00	\$50.00	\$10,000.00
61	780 6002 CNC CRACK REPAIR (DISCRETE)(INJECT)	37.00	LF	\$229.00	\$8,473.00	\$400.00	\$14,800.00
62	3076 6079 D-GR HMA TY-C PG70-22 (EXEMPT)	100.00	TON	\$289.00	\$28,900.00	\$200.00	\$20,000.00
63	3076 6083 D-GR HMA TY-B PG70-22 (EXEMPT)	64.00	TON	\$283.00	\$18,112.00	\$200.00	\$12,800.00
64	4079 6001 PRESTRESSED GROUND ANCHORS	1,125.00	LF	\$123.00	\$138,375.00	\$125.00	\$140,625.00

THE CITY OF ROUND ROCK
 Transportation Department
 3400 Sunrise Road
 Round Rock, Texas 78665



BIDS EXTENDED AND CHECKED
 RESPONSES: 2
 CHECKED BY: Aguirre & Fields
 DATE: 5/8/2025

CERTIFIED BID TABULATION

LOWEST BID

CONTRACT: South Mays Street Wall Stabilization Project				Aaron Concrete Contractors		Austin Filter Systems	
LOCATION: Round Rock TX				Statement of Safety? Yes		Statement of Safety? Yes	
DATE: May 08, 2025				Addendum(s) 1		Addendum(s) 1	
				Bid Bond? Yes		Bid Bond? Yes	
ITEM #	ITEM DESCRIPTION	QTY	UNIT	UNIT PRICE	COST	UNIT PRICE	COST
65	5000 6001 GEOGRID REINFORCE EMBANKMENTS (TY A)	185.00	SY	\$26.00	\$4,810.00	\$10.00	\$1,850.00
66	6001 6002 PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EA	\$20,684.00	\$41,368.00	\$10,000.00	\$20,000.00
67	6185 6002 TMA (STATIONARY)	170.00	DAY	\$379.00	\$64,430.00	\$300.00	\$51,000.00
68	446 6002 CLEAN & PAINT EXIST STR (SYSTEM II)	1.00	LS	\$28,113.00	\$28,113.00	\$50,000.00	\$50,000.00
69	EROSION CONTROL FORCE ACCOUNT	1.00	LS	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00
70	SAFETY CONTINGENCY FORCE ACCOUNT	1.00	LS	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
TOTAL (ITEMS 1-70)					\$2,143,143.36		\$2,046,416.20
TOTAL BASE BID (on final page of bid form)				\$2,143,143.36		\$2,046,416.20	