



REV. 01/16

## Contract Quantity Adjustment/Change Order

EXHIBIT

"A"

Page 1 of 4

Department: Utilities And Environmental Services

Project Name: Kensington Place Asbestos-Cement Waterline Replacement Date: 3/30/21

City Project ID Number: KENAC Change Order/Quantity Adjustment No. 1

Vendor: SKE Construction, LLC Company Name PO Box 1111 Cypress, TX 77410 Address 281-585-4100 Phone No.

## Justification

We under estimated line items 6, 9, 10, 19, 21, 23, 28, and 35. To help balance this out we subtracted the line items that we over estimated.

## SUMMARY

	Amount	% Change
Original Contract Price:	\$1,672,874.73	
Previous Quantity Adjustment(s):		
This Quantity Adjustment:	\$73,611.58	
Total Quantity Adjustment(s):	\$73,611.58	
Total Contract Price with Quantity Adjustment(s):	\$1,746,486.31	
Previous Change Order(s):		0%
This Change Order:		0%
Total Change Order(s) To Date:	\$0.00	0%
Adjusted Contract Price [Original Contract Price Plus Quantity Adjustment(s) Plus Change Order(s)]:	\$1,746,486.31	
Difference between Original and Adjusted Contract Prices:	\$73,611.58	
Original Contract Time:	150	
Time Adjustment by previous Quan. Adj./Change Order:		
Time Adjustment by this Quan. Adj./Change Order:		
New Contract Time:	150	

Prepared By: Shelly A. Eberhart Signature Shelly A. Eberhart, President/CEO, SKE Construction, LLC Printed Name, Title, Company 3/30/21 Date

Contractor: Shelly A. Eberhart Signature Shelly A. Eberhart, President/CEO, SKE Construction LLC Printed Name, Title, Company 3/30/21 Date

City Project Manager: Juan Martinez Signature Juan Martinez, Engineer Associate Printed Name, Title 4/14/21 Date

Mayor/City Manager: \_\_\_\_\_ Signature \_\_\_\_\_ Printed Name, Title \_\_\_\_\_ Date

Project Name: Kensington Place Asbestos-Cement Waterline Replacement

### Change Order Data

[illegible]



# Contract Quantity Adjustment/Change Order

Project Name: Kensington Place Asbestos-Cement Waterline Replacement

Quan. Adj./Change Order No.: 1

## Quantity Adjustment Data

Bid Item #	Item Description	Unit	Qty.	Unit Price	Amount	Contract Time Adjustment (Days)
2	TRENCH SAFETY SYSTEMS INCLUDING PLAN SIGNED AND SEALED BY REGISTERED PROFESSIONAL ENGINEER IN TEXAS	LS	-1	\$1,500.00	-\$1,500.00	
4	EROSION CONTROL LOGS FOR CURB INLET PROTECTION, AS PER DETAIL EC-13	LF	-850	\$8.00	-\$6,800.00	
5	FOR DEPTHS OF 5' OR LESS, COORDINATE AND PERFORM LOCATION AND MARKING OF ALL BURIED EXISTING UTILITIES PRIOR TO COMMENCING WORK (EXAMPLE: BURIED CABLES, FIBER OPTICSM GAS LINES, ETC). PERFORM PRE-CHLORINATED PIPE BURSTING OF EXISTING 8" ASBESTOS CEMENT WATER LINE, REPLACE WITH 8" HDPE DR11 WATER LINE, COMPLETE, INCLUDING EXCAVATIONS, BACKFILL, HYDROSTATIC PRESSURE TESTING, POST-BURSTING CLOSED CIRCUIT TV INSPECTION OF ALL SANITARY SEWER LINES AS DESCRIBED IN ATTACHEMENT A OF SECTION 01000 (TECHNICAL SPECIFICATIONS) AND DELIVER TO CITY, REPLACEMENT OR REPAIR OF MAILBOXES, FENCING, LANDSCAPE AND IRRIGATION SYSTEMS WITH REVEGETATION (SOD), SAME VARIETY AS REMOVED	LF	-1350	\$72.50	-\$97,875.00	
6	FOR DEPTHS OF 5' OR LESS, COORDINATE AND PERFORM LOCATION AND MARKING OF ALL BURIED EXISTING UTILITIES PRIOR TO COMMENCING WORK (EXAMPLE: BURIED CABLES, FIBER OPTICSM GAS LINES, ETC). PERFORM PRE-CHLORINATED PIPE BURSTING OF EXISTING 6" ASBESTOS CEMENT WATER LINE, REPLACE WITH 8" HDPE DR11 WATER LINE, COMPLETE, INCLUDING EXCAVATIONS, BACKFILL, HYDROSTATIC PRESSURE TESTING, POST-BURSTING CLOSED CIRCUIT TV INSPECTION OF ALL SANITARY SEWER LINES AS DESCRIBED IN ATTACHEMENT A OF SECTION 01000 (TECHNICAL SPECIFICATIONS) AND DELIVER TO CITY, REPLACEMENT OR REPAIR OF MAILBOXES, FENCING, LANDSCAPE AND IRRIGATION SYSTEMS WITH REVEGETATION (SOD), SAME VARIETY AS REMOVED	LF	255	\$77.00	\$19,635.00	
8	FOR DEPTHS GREATER THAN 5', COORDINATE AND PERFORM LOCATION AND MARKING OF ALL BURIED EXISTING UTILITIES PRIOR TO COMMENCING WORK (EXAMPLE: BURIED CABLES, FIBER OPTICSM GAS LINES, ETC). PERFORM PRE-CHLORINATED PIPE BURSTING OF EXISTING 8" ASBESTOS CEMENT WATER LINE, REPLACE WITH 8" HDPE DR11 WATER LINE, COMPLETE, INCLUDING EXCAVATIONS, BACKFILL, HYDROSTATIC PRESSURE TESTING, POST-BURSTING CLOSED CIRCUIT TV INSPECTION OF ALL SANITARY SEWER LINES AS DESCRIBED IN ATTACHEMENT A OF SECTION 01000 (TECHNICAL SPECIFICATIONS) AND DELIVER TO CITY, REPLACEMENT OR REPAIR OF MAILBOXES, FENCING, LANDSCAPE AND IRRIGATION SYSTEMS WITH REVEGETATION (SOD), SAME VARIETY AS REMOVED	LF	-100	\$120.00	-\$12,000.00	
9	FOR DEPTHS OF 5' OR LESS, FURNISH AND INSTALL SHORT SINGLE SERVICE, INCLUDING 1" SERVICE SADDLE (EPOXY COATED WITH DUAL SST BANDS) 1" FORD OR APPROVED EQUAL BRASS CORPORATION STOP, 1" POLYETHYLENE DR9 WATER SERVICE TUBING, 1" X 5/8" FORD OR APPROVED EQUAL, LOCKING ANGLE STOP, AS PER DETAIL DRAWING NO, WT-02	EA	4	\$800.00	\$3,200.00	
10	FOR DEPTHS OF 5' OR LESS, FURNISH AND INSTALL LONG SINGLE SERVICE, INCLUDING 1" SERVICE SADDLE (EPOXY COATED WITH DUAL SST BANDS) 1" FORD OR APPROVED EQUAL BRASS CORPORATION STOP, 1" POLYETHYLENE DR9 WATER SERVICE TUBING, 1" X 5/8" FORD OR APPROVED EQUAL, LOCKING ANGLE STOP, AS PER DETAIL DRAWING NO, WT-02	EA	8	\$850.00	\$6,800.00	
11	FOR DEPTHS OF 5' OR LESS, FURNISH AND INSTALL SHORT DUAL SERVICE, INCLUDING 1-1/2" SERVICE SADDLE (EPOXY COATED WITH DUAL SST BANDS) 2" FORD OR APPROVED EQUAL BRASS CORPORATION STOP, 1-1/2" POLYETHYLENE DR9 WATER SERVICE TUBING, 1-1/2" X 3/4" MIP FORD OR APPROVED EQUAL U-BRANCH, 2-3/4X5/8" FIT FORD OR APPROVED EQUAL LOCKING ANGLE STOP, AS PER DETAIL DRAWING NO, WT-04	EA	-22	\$850.00	-\$18,700.00	
12	FOR DEPTHS OF 5' TO 10', FURNISH AND INSTALL SHORT DUAL SERVICE, INCLUDING 1-1/2" SERVICE SADDLE (EPOXY COATED WITH DUAL SST BANDS) 2" FORD OR APPROVED EQUAL BRASS CORPORATION STOP, 1-1/2" POLYETHYLENE DR9 WATER SERVICE TUBING, 1-1/2" X 3/4" MIP FORD OR APPROVED EQUAL U-BRANCH, 2-3/4X5/8" FIT FORD OR APPROVED EQUAL LOCKING ANGLE STOP, AS PER DETAIL DRAWING NO, WT-04	EA	-2	\$900.00	-\$1,800.00	

## rev, 01/16

[illegible]