

**City of Round Rock**  
**Gattis School Rd Wastewater Improvements**  
**Bids Opened: 11/29/18 at 2:00 pm**

<b>BID TABULATION</b>	<b>Austin Underground, Inc.</b>	<b>Austin Engineering Company, Inc.</b>	<b>Whitestone Civil Construction, LLC</b>	<b>Sanat Clara Construction, Ltd.</b>	<b>Lee Contractors, Inc.</b>	<b>Smith Contracting Company, Inc.</b>	<b>Jimmy Evans Company</b>
Addenda Acknowledged (Y/N)	Y	Y	Y	Y	Y	Y	Y
Bid Security (Y/N)	Y	Y	Y	Y	Y	Y	Y
Statement of Bidder's Safety Experience (Y/N)	Y	Y	Y	Y	Y	Y	Y <sup>2</sup>

<b>Bid No. 1: Grading, Paving, and Drainage Items</b>																	
<b>Bid Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>
1	Mobilization (Maximum 5% of total bid), complete in place per Specification 700.	1	LS	\$ 33,000.00	\$ 33,000.00	\$ 25,000.00	\$ 25,000.00	\$ 28,000.00	\$ 28,000.00	\$ 35,900.00	\$ 35,900.00	\$ 39,500.00	\$ 39,500.00	\$ 37,000.00	\$ 37,000.00	\$ 36,350.00	\$ 36,350.00
2	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0 -10 ft deep, complete in place per Specification 510.	815	LF	\$ 65.00	\$ 52,975.00	\$ 90.00	\$ 73,350.00	\$ 75.00	\$ 61,125.00	\$ 73.00	\$ 59,495.00	\$ 62.00	\$ 50,530.00	\$ 70.00	\$ 57,050.00	\$ 73.20	\$ 59,658.00
3	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill 10 -14 ft deep, complete in place per Specification 510.	754	LF	\$ 80.00	\$ 60,320.00	\$ 107.00	\$ 80,678.00	\$ 85.00	\$ 64,090.00	\$ 97.00	\$ 73,138.00	\$ 84.00	\$ 63,336.00	\$ 90.00	\$ 67,860.00	\$ 96.90	\$ 73,062.60
4	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 14 - 18 ft deep, complete in place per Specification 510.	466	LF	\$ 120.00	\$ 55,920.00	\$ 128.00	\$ 59,648.00	\$ 92.00	\$ 42,872.00	\$ 130.00	\$ 60,580.00	\$ 95.00	\$ 44,270.00	\$ 120.00	\$ 55,920.00	\$ 129.30	\$ 60,253.80
5	Furnish and Install 8" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0-10 ft deep, complete in place per Specification 510.	570	LF	\$ 50.00	\$ 28,500.00	\$ 73.00	\$ 41,610.00	\$ 55.00	\$ 31,350.00	\$ 42.00	\$ 23,940.00	\$ 45.00	\$ 25,650.00	\$ 50.00	\$ 28,500.00	\$ 55.00	\$ 31,350.00
6	Furnish and Install 8" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10-14 ft deep, complete in place per Specification 510.	228	LF	\$ 70.00	\$ 15,960.00	\$ 78.00	\$ 17,784.00	\$ 56.00	\$ 12,768.00	\$ 54.00	\$ 12,312.00	\$ 58.00	\$ 13,224.00	\$ 60.00	\$ 13,680.00	\$ 64.25	\$ 14,649.00
7	Furnish and Install 8" C-900 (DR-25) PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 14-18 ft deep, complete in place per Specification 510.	24	LF	\$ 80.00	\$ 1,920.00	\$ 121.00	\$ 2,904.00	\$ 65.00	\$ 1,560.00	\$ 157.00	\$ 3,768.00	\$ 200.00	\$ 4,800.00	\$ 140.00	\$ 3,360.00	\$ 161.40	\$ 3,873.60
8	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0-10 ft deep, complete in place per Specification 510.	93	LF	\$ 85.00	\$ 7,905.00	\$ 93.00	\$ 8,649.00	\$ 70.00	\$ 6,510.00	\$ 77.00	\$ 7,161.00	\$ 75.00	\$ 6,975.00	\$ 70.00	\$ 6,510.00	\$ 80.75	\$ 7,509.75
9	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10 - 16 ft deep, complete in place per Specification 510.	128	LF	\$ 120.00	\$ 15,360.00	\$ 112.00	\$ 14,336.00	\$ 82.00	\$ 10,496.00	\$ 107.00	\$ 13,696.00	\$ 105.00	\$ 13,440.00	\$ 90.00	\$ 11,520.00	\$ 111.25	\$ 14,240.00
10	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 16 -22 ft deep, complete in place per Specification 510.	74	LF	\$ 130.00	\$ 9,620.00	\$ 135.00	\$ 9,990.00	\$ 115.00	\$ 8,510.00	\$ 165.00	\$ 12,210.00	\$ 135.00	\$ 9,990.00	\$ 120.00	\$ 8,880.00	\$ 167.85	\$ 12,420.90
11	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0 - 10 ft deep, complete in place per Specification 510.	92	LF	\$ 65.00	\$ 5,980.00	\$ 76.00	\$ 6,992.00	\$ 60.00	\$ 5,520.00	\$ 45.00	\$ 4,140.00	\$ 54.00	\$ 4,968.00	\$ 60.00	\$ 5,520.00	\$ 64.75	\$ 5,957.00
12	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10 - 16 ft deep, complete in place per Specification 510.	127	LF	\$ 66.00	\$ 8,382.00	\$ 84.00	\$ 10,668.00	\$ 68.00	\$ 8,636.00	\$ 61.00	\$ 7,747.00	\$ 90.00	\$ 11,430.00	\$ 70.00	\$ 8,890.00	\$ 78.50	\$ 9,969.50
13	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 16 - 22 ft deep, complete in place per Specification 510.	74	LF	\$ 100.00	\$ 7,400.00	\$ 88.00	\$ 6,512.00	\$ 85.00	\$ 6,290.00	\$ 90.00	\$ 6,660.00	\$ 125.00	\$ 9,250.00	\$ 90.00	\$ 6,660.00	\$ 100.10	\$ 7,407.40
14	Furnish and Install 6" SDR 26 PVC Pipe for service line, with standard bedding and backfill and clean-out, 13 ft deep, complete in place per Specification 510.	10	LF	\$ 170.00	\$ 1,700.00	\$ 380.00	\$ 3,800.00	\$ 100.00	\$ 1,000.00	\$ 71.00	\$ 710.00	\$ 52.00	\$ 520.00	\$ 100.00	\$ 1,000.00	\$ 101.85	\$ 1,018.50
15	Furnish and Install Standard City of Round Rock 4-Foot Dia. Sanitary Sewer Manhole with 4' Riser and Bolted Cover, 0 - 8 ft deep, complete in place per Specification 506.	9	EA	\$ 5,400.00	\$ 48,600.00	\$ 4,600.00	\$ 41,400.00	\$ 7,000.00	\$ 63,000.00	\$ 5,000.00	\$ 45,000.00	\$ 5,000.00	\$ 45,000.00	\$ 5,700.00	\$ 51,300.00	\$ 6,500.00	\$ 58,500.00
16	Furnish and Install Extra Depth on 4-foot Dia. Sanitary Sewer Manhole with 4' Riser, Depth: 8 - 18 ft, complete in place per Specification 506.	34	VF	\$ 430.00	\$ 14,620.00	\$ 300.00	\$ 10,200.00	\$ 400.00	\$ 13,600.00	\$ 350.00	\$ 11,900.00	\$ 550.00	\$ 18,700.00	\$ 600.00	\$ 20,400.00	\$ 447.30	\$ 15,208.20
17	Furnish and Install Standard City of Round Rock 5-Foot Dia. Sanitary Sewer Manhole with 5' Riser and Bolted Cover, 0 - 22 ft deep, complete in place per Specification 506.	1	EA	\$ 17,000.00	\$ 17,000.00	\$ 9,000.00	\$ 9,000.00	\$ 15,000.00	\$ 15,000.00	\$ 14,000.00	\$ 14,000.00	\$ 22,500.00	\$ 22,500.00	\$ 13,300.00	\$ 13,300.00	\$ 17,605.00	\$ 17,605.00
18	Furnish and Install Standard Manhole External Drop Connection, up to 7 feet of drop, complete in place per Specification 506.	1	EA	\$ 2,700.00	\$ 2,700.00	\$ 1,000.00	\$ 1,000.00	\$ 4,000.00	\$ 4,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,500.00	\$ 5,500.00	\$ 2,000.00	\$ 2,000.00	\$ 6,965.00	\$ 6,965.00



**City of Round Rock**  
**Gattis School Rd Wastewater Improvements**  
**Bids Opened: 11/29/18 at 2:00 pm**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount
19	Furnish and Install City of Round Rock Standard Manhole Internal Drop Connection, up to 14 feet of drop, complete in place per Specification 506.	1	EA	\$ 4,200.00	\$ 4,200.00	\$ 1,200.00	\$ 1,200.00	\$ 3,750.00	\$ 3,775.00	\$ 7,000.00	\$ 7,000.00	\$ 9,500.00	\$ 9,500.00	\$ 2,500.00	\$ 2,500.00	\$ 9,070.00	\$ 9,070.00
20	Furnish and Install Manhole Vent and Ball Check Valve where shown on the plans, complete in place per Specification 506.	2	EA	\$ 4,600.00	\$ 9,200.00	\$ 4,000.00	\$ 8,000.00	\$ 5,000.00	\$ 10,000.00	\$ 4,000.00	\$ 8,000.00	\$ 8,500.00	\$ 17,000.00	\$ 5,700.00	\$ 11,400.00	\$ 6,645.00	\$ 13,290.00
21	Furnish and Install all Materials, Labor, and Equipment to core existing manhole and connect 10" PVC pipe including reshaping invert channel, recoating interior surface, adding bolts to existing manhole lid, and appurtenances, complete in place per Specification 506.	1	LS	\$ 6,200.00	\$ 6,200.00	\$ 3,000.00	\$ 3,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,500.00	\$ 5,500.00	\$ 8,600.00	\$ 8,600.00	\$ 9,500.00	\$ 9,500.00
22	Furnish and Install 18" Steel Casing Pipe (1/4" wall thickness) by open cut, not including 8" carrier pipe, including appurtenances, complete in place per Specification 510.	37	LF	\$ 140.00	\$ 5,180.00	\$ 100.00	\$ 3,700.00	\$ 135.00	\$ 4,995.00	\$ 206.00	\$ 7,622.00	\$ 130.00	\$ 4,810.00	\$ 100.00	\$ 3,700.00	\$ 127.35	\$ 4,711.95
23	Furnish and Install 20" Steel Casing Pipe (5/16" wall thickness) by open cut, not including 10" carrier pipe, including appurtenances, complete in place per Specification 510.	459	LF	\$ 120.00	\$ 55,080.00	\$ 135.00	\$ 61,965.00	\$ 180.00	\$ 82,620.00	\$ 264.00	\$ 121,176.00	\$ 140.00	\$ 64,260.00	\$ 120.00	\$ 55,080.00	\$ 132.00	\$ 60,588.00
24	Furnish and Install Type B concrete trench cap, complete in place per Specification 505.	13.2	CY	\$ 180.00	\$ 2,376.00	\$ 200.00	\$ 2,640.00	\$ 200.00	\$ 2,640.00	\$ 500.00	\$ 6,600.00	\$ 250.00	\$ 3,300.00	\$ 400.00	\$ 5,280.00	\$ 147.25	\$ 1,943.70
25	Furnish and Install 300 psi flowable fill encasement, complete in place per Specification 402.	3.8	CY	\$ 220.00	\$ 836.00	\$ 250.00	\$ 950.00	\$ 175.00	\$ 665.00	\$ 500.00	\$ 1,900.00	\$ 500.00	\$ 1,900.00	\$ 160.00	\$ 608.00	\$ 102.50	\$ 389.50
26	Furnish and Install 8" Ductile Iron Pipe (Class 350 psi) including fittings, joint restraints, polyethylene wrap, thrust blocking, rock excavation as necessary, dewatering, surface restoration, disposal of excess material, cleaning, flushing, disinfection, pressure testing, and appurtenances with standard bedding and backfill, complete in place per Specification 510.	40	LF	\$ 110.00	\$ 4,400.00	\$ 100.00	\$ 4,000.00	\$ 300.00	\$ 12,000.00	\$ 173.00	\$ 6,920.00	\$ 126.50	\$ 5,060.00	\$ 100.00	\$ 4,000.00	\$ 143.55	\$ 5,742.00
27	Furnish and Install 12" Ductile Iron Pipe (Class 350 psi) including connection to existing waterline, fittings, joint restraints, polyethylene wrap, thrust blocking, rock excavation as necessary, dewatering, surface restoration, disposal of excess material, cleaning, flushing, disinfection, pressure testing, and appurtenances with standard bedding and backfill, complete in place per Specification 510.	136	LF	\$ 130.00	\$ 17,680.00	\$ 215.00	\$ 29,240.00	\$ 300.00	\$ 40,800.00	\$ 217.00	\$ 29,512.00	\$ 227.50	\$ 30,940.00	\$ 112.00	\$ 15,232.00	\$ 164.35	\$ 22,351.60
28	Furnish and Install 24" Steel Casing Pipe (1/2" wall thickness) by bore and jack, not including 12" waterline carrier pipe, including access pits and appurtenances, complete in place per Specification 510.	106	LF	\$ 490.00	\$ 51,940.00	\$ 400.00	\$ 42,400.00	\$ 650.00	\$ 68,900.00	\$ 500.00	\$ 53,000.00	\$ 425.00	\$ 45,050.00	\$ 400.00	\$ 42,400.00	\$ 554.40	\$ 58,766.40
29	Furnish and Install Standard 2" Blow-Off, complete in place per Specification 511.	2	EA	\$ 1,600.00	\$ 3,200.00	\$ 1,200.00	\$ 2,400.00	\$ 2,300.00	\$ 4,600.00	\$ 1,300.00	\$ 2,600.00	\$ 3,500.00	\$ 7,000.00	\$ 1,800.00	\$ 3,600.00	\$ 3,025.00	\$ 6,050.00
30	Furnish and Install 8" Gate Valve with box, valve extension, and locking debris cap, complete in place per Specification 511.	2	EA	\$ 1,700.00	\$ 3,400.00	\$ 1,825.00	\$ 3,650.00	\$ 1,900.00	\$ 3,800.00	\$ 2,000.00	\$ 4,000.00	\$ 1,650.00	\$ 3,300.00	\$ 1,900.00	\$ 3,800.00	\$ 1,230.00	\$ 2,460.00
31	Furnish and Install 12" Gate Valve with box, valve extension, and locking debris cap, complete in place per Specification 511.	4	EA	\$ 3,100.00	\$ 12,400.00	\$ 3,000.00	\$ 12,000.00	\$ 3,000.00	\$ 12,000.00	\$ 3,500.00	\$ 14,000.00	\$ 2,250.00	\$ 9,000.00	\$ 2,900.00	\$ 11,600.00	\$ 2,195.00	\$ 8,780.00
32	Furnish all Materials, Labor, and Equipment to Salvage and Reinstall Existing Fences along water and sewer line route, complete in place per Specification 702.	1	LS	\$ 5,100.00	\$ 5,100.00	\$ 2,500.00	\$ 2,500.00	\$ 3,000.00	\$ 3,000.00	\$ 2,000.00	\$ 2,000.00	\$ 10,500.00	\$ 10,500.00	\$ 10,500.00	\$ 10,500.00	\$ 12,715.00	\$ 12,715.00
33	Furnish all Materials, Labor, and Equipment to Remove and Replace existing asphalt road and driveways damaged during construction including obtaining required Williamson County permits and providing Williamson County performance bond per plans, complete in place per Specification 340.	40	SY	\$ 210.00	\$ 8,400.00	\$ 125.00	\$ 5,000.00	\$ 200.00	\$ 8,000.00	\$ 50.00	\$ 2,000.00	\$ 200.00	\$ 8,000.00	\$ 300.00	\$ 12,000.00	\$ 105.65	\$ 4,226.00
34	Furnish all Materials, Labor, and Equipment to Remove and Replace existing gravel driveway and sidewalk damaged during construction per plans, complete in place per Specification 101.	28	SY	\$ 93.00	\$ 2,604.00	\$ 25.00	\$ 700.00	\$ 100.00	\$ 2,800.00	\$ 20.00	\$ 560.00	\$ 75.00	\$ 2,100.00	\$ 30.00	\$ 840.00	\$ 250.00	\$ 7,000.00
35	Furnish all Materials, Labor, and Equipment to Remove and Replace existing concrete sidewalk damaged during construction per plans, complete in place per Specification 432.	6	SY	\$ 420.00	\$ 2,520.00	\$ 100.00	\$ 600.00	\$ 100.00	\$ 600.00	\$ 300.00	\$ 1,800.00	\$ 500.00	\$ 3,000.00	\$ 100.00	\$ 600.00	\$ 1,595.00	\$ 9,570.00
36	Clearing and Grubbing of Areas as required within Street Right-of-Way and Easements including demolition and removal of trees where shown on the plans and off-site disposal of cleared and grubbed material, complete in place per Specification 102.	2.6	AC	\$ 3,300.00	\$ 8,580.00	\$ 3,000.00	\$ 7,800.00	\$ 4,000.00	\$ 10,400.00	\$ 2,500.00	\$ 6,500.00	\$ 2,500.00	\$ 6,500.00	\$ 11,000.00	\$ 28,600.00	\$ 6,895.00	\$ 17,927.00
37	Pollution Prevention Implementation including Storm Water Pollution Prevention Plan, Maintenance, Permitting, Inspections, and Reporting for all Pollution Prevention Measures as shown on the plans, complete in place per Drawing 00G-03.	1	LS	\$ 900.00	\$ 900.00	\$ 3,000.00	\$ 3,000.00	\$ 3,000.00	\$ 3,000.00	\$ 4,000.00	\$ 4,000.00	\$ 250.00	\$ 250.00	\$ 4,500.00	\$ 4,500.00	\$ 5,890.00	\$ 5,890.00
38	Furnish, Install, Maintain and Remove Temporary Chain Link Fencing around contractor's lay down area, complete in place per Specification 701.	830	LF	\$ 8.00	\$ 6,640.00	\$ 15.00	\$ 12,450.00	\$ 6.00	\$ 4,980.00	\$ 4.00	\$ 3,320.00	\$ 15.00	\$ 12,450.00	\$ 15.00	\$ 12,450.00	\$ 9.30	\$ 7,719.00
39	Furnish, Install, Maintain and Remove temporary moving Chain Link Fence around any construction equipment and open trenches within cattle pen, complete in place per Specification 701.	1	LS	\$ 500.00	\$ 500.00	\$ 2,500.00	\$ 2,500.00	\$ 1,000.00	\$ 1,000.00	\$ 2,000.00	\$ 2,000.00	\$ 3,000.00	\$ 3,000.00	\$ 11,000.00	\$ 11,000.00	\$ 3,535.00	\$ 3,535.00
40	Furnish, Install, Maintain and Remove Concrete Washout, complete in place per Drawing 00G-03.	1	EA	\$ 500.00	\$ 500.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 500.00	\$ 500.00	\$ 750.00	\$ 750.00	\$ 700.00	\$ 700.00	\$ 2,350.00	\$ 2,350.00
41	Furnish, Install, Maintain and Remove Stabilized Construction Access as shown on the plans, complete in place per Specification 641.	2	EA	\$ 1,000.00	\$ 2,000.00	\$ 1,200.00	\$ 2,400.00	\$ 1,400.00	\$ 2,800.00	\$ 2,000.00	\$ 4,000.00	\$ 1,500.00	\$ 3,000.00	\$ 2,000.00	\$ 4,000.00	\$ 1,865.00	\$ 3,730.00



**City of Round Rock  
Gattis School Rd Wastewater Improvements  
Bids Opened: 11/29/18 at 2:00 pm**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount
42	Furnish and Install Filter Fabric Fence or 12" dia. Mulch Logs (staked at a maximum of 8 ft spacing per plans) including removal upon conclusion of work. Install all filter fabric or mulch logs for the site prior to any other construction, complete in place per Specification 642.	3,877	LF	\$ 2.00	\$ 7,754.00	\$ 3.00	\$ 11,631.00	\$ 3.00	\$ 11,631.00	\$ 3.00	\$ 11,631.00	\$ 2.00	\$ 7,754.00	\$ 2.25	\$ 8,723.25	\$ 4.00	\$ 15,508.00
43	Furnish, Install, Maintain and Remove Creek Crossing appurtenances per Plans, complete in place per Specification 642.	1	LS	\$ 5,000.00	\$ 5,000.00	\$ 15,000.00	\$ 15,000.00	\$ 2,500.00	\$ 2,500.00	\$ 2,000.00	\$ 2,000.00	\$ 6,500.00	\$ 6,500.00	\$ 40,000.00	\$ 40,000.00	\$ 4,190.85	\$ 4,190.85
44	Furnish, Install, Maintain, and Remove Chain Link Fence Tree Protection, complete in place per Specification 610.	34	LF	\$ 4.00	\$ 136.00	\$ 3.50	\$ 119.00	\$ 4.00	\$ 136.00	\$ 5.00	\$ 170.00	\$ 10.00	\$ 340.00	\$ 6.00	\$ 204.00	\$ 17.35	\$ 589.90
45	Furnish, Install, Maintain, and Remove Wood Slats Fence Tree Protection, complete in place per Specification 610.	11	Per Tree	\$ 190.00	\$ 2,090.00	\$ 110.00	\$ 1,210.00	\$ 75.00	\$ 825.00	\$ 100.00	\$ 1,100.00	\$ 250.00	\$ 2,750.00	\$ 500.00	\$ 5,500.00	\$ 361.45	\$ 3,975.95
46	Furnish and Install Hydromulch Seeding of disturbed areas based on 20 ft wide by 3,445 ft long plus the construction laydown area. Additional area disturbed by contractor shall be restored at his cost, complete in place per Specification 604.	2.6	AC	\$ 8,400.00	\$ 21,840.00	\$ 4,840.00	\$ 12,584.00	\$ 2,000.00	\$ 5,200.00	\$ 2,000.00	\$ 5,200.00	\$ 7,800.00	\$ 20,280.00	\$ 3,700.00	\$ 9,620.00	\$ 3,665.00	\$ 9,529.00
47	Furnish, Install, and Maintain watering and/or temporary irrigation system until revegetation is established per City specifications, complete in place per Specification 604.	2.6	AC	\$ 5,300.00	\$ 13,780.00	\$ 2,420.00	\$ 6,292.00	\$ 3,000.00	\$ 7,800.00	\$ 2,000.00	\$ 5,200.00	\$ 3,000.00	\$ 7,800.00	\$ 8,000.00	\$ 20,800.00	\$ 11,965.00	\$ 31,109.00
48	Furnish and Install Trench Safety System Plan, complete in place per Specification 509.	3,621	LF	\$ 3.00	\$ 10,863.00	\$ 1.00	\$ 3,621.00	\$ 4.00	\$ 14,484.00	\$ 1.00	\$ 3,621.00	\$ 8.50	\$ 30,778.50	\$ 1.00	\$ 3,621.00	\$ 8.50	\$ 30,778.50
49	Furnish and Install Project Sign including all Material and Labor, complete in place per Specification 802.	1	EA	\$ 500.00	\$ 500.00	\$ 650.00	\$ 650.00	\$ 1,100.00	\$ 1,100.00	\$ 1,000.00	\$ 1,000.00	\$ 750.00	\$ 750.00	\$ 800.00	\$ 800.00	\$ 1,800.00	\$ 1,800.00
50	Furnish, Install, and Maintain Traffic Control Plan and Traffic Control Devices along water and sewer line route with signage, safety barriers, and appurtenances, in accordance with plans, complete in place per Specification 803.	1	LS	\$ 1,300.00	\$ 1,300.00	\$ 10,000.00	\$ 10,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 16,500.00	\$ 16,500.00	\$ 35,000.00	\$ 35,000.00	\$ 9,325.00	\$ 9,325.00
51	Steel Plating or Temporary Driveway diversions to provide access to private lots during construction as necessary, complete in place per Specification 510.	6	EA	\$ 66.00	\$ 396.00	\$ 250.00	\$ 1,500.00	\$ 500.00	\$ 3,000.00	\$ 1,000.00	\$ 6,000.00	\$ 1,250.00	\$ 7,500.00	\$ 2,000.00	\$ 12,000.00	\$ 1,090.00	\$ 6,540.00
52				\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
53				\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	<b>TOTAL AMOUNT BID No. 1</b>				<b>\$ 665,357.00</b>	<sup>1</sup>	<b>\$ 699,723.00</b>	<sup>8</sup>	<b>\$ 725,878.00</b>		<b>\$ 732,289.00</b>		<b>\$ 746,705.50</b>		<b>\$ 788,608.25</b>	<sup>10</sup>	<b>\$ 827,649.60</b>

**Apparent Low Bidder (Austin Underground, Inc.) = \$665,357.00**

<sup>1</sup> amount on bid doc = \$627,723.00

<sup>2</sup> Statement of Bidder's Safety Experience is not signed.

<sup>3</sup> No OSHA Logs attached.

<sup>4</sup> unit price multiplied by quantity does not equal amount on bid doc

<sup>5</sup> amount on bid doc = \$1,225,848.80

<sup>6</sup> Error in quantity on Bid Form

<sup>7</sup> Written Unit Price does not match Unit Price

<sup>8</sup> amount on bid doc = \$725,853.00

<sup>9</sup> words match Amount and not Unit Price

<sup>10</sup> amount on bid doc = \$828,249.60

<sup>11</sup> Written Unit Price match Amount on all Items

**City of Round Rock**  
**Gattis School Rd Wastewater Improvements**  
**Bids Opened: 11/29/18 at 2:00 pm**

<b>BID TABULATION</b>	<b>Patin Construction, LLC</b>	<b>Peabody General Contractors</b>	<b>Nerie Construction, LLC</b>	<b>Prota Construction Inc, &amp; Prota Inc., JVC</b>
Addenda Acknowledged (Y/N)	Y	Y	Y	Y
Bid Security (Y/N)	Y	Y	Y	Y
Statement of Bidder's Safety Experience (Y/N)	Y	Y	Y <sup>3</sup>	Y

<b>Bid No. 1: Grading, Paving, and Drainage Items</b>												
<b>Bid Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>	
1	Mobilization (Maximum 5% of total bid), complete in place per Specification 700.	1	LS	\$ 46,000.00	\$ 46,000.00	\$ 35,000.00	\$ 35,000.00 <sup>11</sup>	\$ 48,000.00	\$ 48,000.00	\$ 56,200.00	\$ 56,200.00	
2	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0 -10 ft deep, complete in place per Specification 510.	815	LF	\$ 70.00	\$ 57,050.00	\$ 85.00	\$ 69,275.00	\$ 115.00	\$ 93,725.00	\$ 140.00	\$ 114,100.00	
3	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill 10 -14 ft deep, complete in place per Specification 510.	754	LF	\$ 75.00	\$ 56,550.00	\$ 105.00	\$ 79,170.00	\$ 150.00	\$ 113,100.00	\$ 152.00	\$ 114,608.00	
4	Furnish and Install 8" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 14 - 18 ft deep, complete in place per Specification 510.	466	LF	\$ 80.00	\$ 37,280.00	\$ 120.00	\$ 55,920.00	\$ 215.00	\$ 100,190.00	\$ 227.00	\$ 105,782.00	
5	Furnish and Install 8" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0-10 ft deep, complete in place per Specification 510.	570	LF	\$ 70.00	\$ 39,900.00	\$ 65.00	\$ 37,050.00	\$ 55.00	\$ 31,350.00	\$ 103.00	\$ 58,710.00	
6	Furnish and Install 8" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10-14 ft deep, complete in place per Specification 510.	228	LF	\$ 75.00	\$ 17,100.00	\$ 85.00	\$ 19,380.00	\$ 65.00	\$ 14,820.00	\$ 114.00	\$ 25,992.00	
7	Furnish and Install 8" C-900 (DR-25) PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 14-18 ft deep, complete in place per Specification 510.	24	LF	\$ 80.00	\$ 1,920.00	\$ 150.00	\$ 3,600.00	\$ 99.00	\$ 2,376.00	\$ 232.00	\$ 5,568.00	
8	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0-10 ft deep, complete in place per Specification 510.	93	LF	\$ 75.00	\$ 6,975.00	\$ 100.00	\$ 9,300.00	\$ 109.00	\$ 10,137.00	\$ 146.00	\$ 13,578.00	
9	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10 - 16 ft deep, complete in place per Specification 510.	128	LF	\$ 90.00	\$ 11,520.00	\$ 125.00	\$ 16,000.00	\$ 149.00	\$ 19,072.00	\$ 160.00	\$ 20,480.00	
10	Furnish and Install 10" SDR 26 PVC Pipe installed in rock including rock excavation, tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 16 -22 ft deep, complete in place per Specification 510.	74	LF	\$ 130.00	\$ 9,620.00	\$ 220.00	\$ 16,280.00	\$ 232.00	\$ 17,168.00	\$ 252.00	\$ 18,648.00	
11	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 0 - 10 ft deep, complete in place per Specification 510.	92	LF	\$ 75.00	\$ 6,900.00	\$ 70.00	\$ 6,440.00	\$ 65.00	\$ 5,980.00	\$ 105.00	\$ 9,660.00	
12	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 10 - 16 ft deep, complete in place per Specification 510.	127	LF	\$ 90.00	\$ 11,430.00	\$ 90.00	\$ 11,430.00	\$ 75.00	\$ 9,525.00	\$ 111.00	\$ 14,097.00	
13	Furnish and Install 10" SDR 26 PVC Pipe installed in clay including tracer tape, disposal of excess material, and appurtenances with standard bedding and backfill, 16 - 22 ft deep, complete in place per Specification 510.	74	LF	\$ 130.00	\$ 9,620.00	\$ 180.00	\$ 13,320.00	\$ 149.00	\$ 11,026.00	\$ 186.00	\$ 13,764.00	
14	Furnish and Install 6" SDR 26 PVC Pipe for service line, with standard bedding and backfill and clean-out, 13 ft deep, complete in place per Specification 510.	10	LF	\$ 1,000.00	\$ 10,000.00	\$ 210.00	\$ 2,100.00	\$ 65.00	\$ 650.00	\$ 72.00	\$ 720.00	
15	Furnish and Install Standard City of Round Rock 4-Foot Dia. Sanitary Sewer Manhole with 4' Riser and Bolted Cover, 0 - 8 ft deep, complete in place per Specification 506.	9	EA	\$ 8,500.00	\$ 76,500.00	\$ 5,000.00	\$ 45,000.00	\$ 10,000.00	\$ 90,000.00	\$ 6,643.00	\$ 59,787.00	
16	Furnish and Install Extra Depth on 4-foot Dia. Sanitary Sewer Manhole with 4' Riser, Depth: 8 - 18 ft, complete in place per Specification 506.	34	VF	\$ 500.00	\$ 17,000.00	\$ 1,000.00	\$ 34,000.00	\$ 350.00	\$ 11,900.00	\$ 855.00	\$ 29,070.00	
17	Furnish and Install Standard City of Round Rock 5-Foot Dia. Sanitary Sewer Manhole with 5' Riser and Bolted Cover, 0 - 22 ft deep, complete in place per Specification 506.	1	EA	\$ 10,000.00	\$ 10,000.00	\$ 16,000.00	\$ 16,000.00	\$ 65,000.00	\$ 65,000.00	\$ 13,787.00	\$ 13,787.00	
18	Furnish and Install Standard Manhole External Drop Connection, up to 7 feet of drop, complete in place per Specification 506.	1	EA	\$ 12,000.00	\$ 12,000.00	\$ 3,000.00	\$ 3,000.00	\$ 4,500.00	\$ 4,500.00	\$ 12,003.00	\$ 12,003.00	



**City of Round Rock**  
**Gattis School Rd Wastewater Improvements**  
**Bids Opened: 11/29/18 at 2:00 pm**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount
19	Furnish and Install City of Round Rock Standard Manhole Internal Drop Connection, up to 14 feet of drop, complete in place per Specification 506.	1	EA	\$ 15,000.00	\$ 15,000.00	\$ 4,500.00	\$ 4,500.00	\$ 4,500.00	\$ 4,500.00	\$ 11,351.00	\$ 11,351.00
20	Furnish and Install Manhole Vent and Ball Check Valve where shown on the plans, complete in place per Specification 506.	2	EA	\$ 6,500.00	\$ 13,000.00	\$ 4,600.00	\$ 9,200.00	\$ 4,500.00	\$ 9,000.00	\$ 9,997.00	\$ 19,994.00
21	Furnish and Install all Materials, Labor, and Equipment to core existing manhole and connect 10" PVC pipe including reshaping invert channel, recoating interior surface, adding bolts to existing manhole lid, and appurtenances, complete in place per Specification 506.	1	LS	\$ 10,000.00	\$ 10,000.00	\$ 5,500.00	\$ 5,500.00	\$ 3,000.00	\$ 3,000.00	\$ 25,023.00	\$ 25,023.00
22	Furnish and Install 18" Steel Casing Pipe (1/4" wall thickness) by open cut, not including 8" carrier pipe, including appurtenances, complete in place per Specification 510.	37	LF	\$ 140.00	\$ 5,180.00	\$ 125.00	\$ 4,625.00	\$ 150.00	\$ 5,550.00	\$ 143.00	\$ 5,291.00
23	Furnish and Install 20" Steel Casing Pipe (5/16" wall thickness) by open cut, not including 10" carrier pipe, including appurtenances, complete in place per Specification 510.	459	LF	\$ 160.00	\$ 73,440.00	\$ 175.00	\$ 80,325.00	\$ 175.00	\$ 80,325.00	\$ 149.00	\$ 68,391.00
24	Furnish and Install Type B concrete trench cap, complete in place per Specification 505.	13.2	CY	\$ 400.00	\$ 5,280.00	\$ 175.00	\$ 2,310.00	\$ 300.00	\$ 3,960.00	\$ 792.00	\$ 10,454.40
25	Furnish and Install 300 psi flowable fill encasement, complete in place per Specification 402.	3.8	CY	\$ 400.00	\$ 1,520.00	\$ 250.00	\$ 950.00	\$ 250.00	\$ 950.00	\$ 792.00	\$ 3,009.60
26	Furnish and Install 8" Ductile Iron Pipe (Class 350 psi) including fittings, joint restraints, polyethylene wrap, thrust blocking, rock excavation as necessary, dewatering, surface restoration, disposal of excess material, cleaning, flushing, disinfection, pressure testing, and appurtenances with standard bedding and backfill, complete in place per Specification 510.	40	LF	\$ 400.00	\$ 16,000.00	\$ 125.00	\$ 5,000.00	\$ 150.00	\$ 6,000.00	\$ 238.00	\$ 9,520.00
27	Furnish and Install 12" Ductile Iron Pipe (Class 350 psi) including connection to existing waterline, fittings, joint restraints, polyethylene wrap, thrust blocking, rock excavation as necessary, dewatering, surface restoration, disposal of excess material, cleaning, flushing, disinfection, pressure testing, and appurtenances with standard bedding and backfill, complete in place per Specification 510.	136	LF	\$ 500.00	\$ 68,000.00	\$ 175.00	\$ 23,800.00	\$ 250.00	\$ 34,000.00	\$ 232.00	\$ 31,552.00
28	Furnish and Install 24" Steel Casing Pipe (1/2" wall thickness) by bore and jack, not including 12" waterline carrier pipe, including access pits and appurtenances, complete in place per Specification 510.	106	LF	\$ 950.00	\$ 100,700.00	\$ 650.00	\$ 68,900.00	\$ 300.00	\$ 31,800.00	\$ 950.00	\$ 100,700.00
29	Furnish and Install Standard 2" Blow-Off, complete in place per Specification 511.	2	EA	\$ 3,000.00	\$ 6,000.00	\$ 2,500.00	\$ 5,000.00	\$ 2,000.00	\$ 4,000.00	\$ 4,695.00	\$ 9,390.00
30	Furnish and Install 8" Gate Valve with box, valve extension, and locking debris cap, complete in place per Specification 511.	2	EA	\$ 3,000.00	\$ 6,000.00	\$ 1,500.00	\$ 3,000.00	\$ 3,000.00	\$ 6,000.00	\$ 1,805.00	\$ 3,610.00
31	Furnish and Install 12" Gate Valve with box, valve extension, and locking debris cap, complete in place per Specification 511.	4	EA	\$ 4,500.00	\$ 18,000.00	\$ 2,500.00	\$ 10,000.00	\$ 4,000.00	\$ 16,000.00	\$ 3,334.00	\$ 13,336.00
32	Furnish all Materials, Labor, and Equipment to Salvage and Reinstall Existing Fences along water and sewer line route, complete in place per Specification 702.	1	LS	\$ 5,000.00	\$ 5,000.00	\$ 6,000.00	\$ 6,000.00	\$ 1,500.00	\$ 1,500.00	\$ 17,807.00	\$ 17,807.00
33	Furnish all Materials, Labor, and Equipment to Remove and Replace existing asphalt road and driveways damaged during construction including obtaining required Williamson County permits and providing Williamson County performance bond per plans, complete in place per Specification 340.	40	SY	\$ 500.00	\$ 20,000.00	\$ 90.00	\$ 3,600.00	\$ 150.00	\$ 6,000.00	\$ 70.00	\$ 2,800.00
34	Furnish all Materials, Labor, and Equipment to Remove and Replace existing gravel driveway and sidewalk damaged during construction per plans, complete in place per Specification 101.	28	SY	\$ 500.00	\$ 14,000.00	\$ 75.00	\$ 2,100.00	\$ 60.00	\$ 1,680.00	\$ 62.00	\$ 1,736.00
35	Furnish all Materials, Labor, and Equipment to Remove and Replace existing concrete sidewalk damaged during construction per plans, complete in place per Specification 432.	6	SY	\$ 500.00	\$ 3,000.00	\$ 110.00	\$ 660.00	\$ 110.00	\$ 660.00	\$ 130.00	\$ 780.00
36	Clearing and Grubbing of Areas as required within Street Right-of-Way and Easements including demolition and removal of trees where shown on the plans and off-site disposal of cleared and grubbed material, complete in place per Specification 102.	2.6	AC	\$ 3,500.00	\$ 9,100.00	\$ 1,500.00	\$ 3,900.00	\$ 6,000.00	\$ 15,600.00	\$ 3,957.00	\$ 10,288.20
37	Pollution Prevention Implementation including Storm Water Pollution Prevention Plan, Maintenance, Permitting, Inspections, and Reporting for all Pollution Prevention Measures as shown on the plans, complete in place per Drawing 00G-03.	1	LS	\$ 2,500.00	\$ 2,500.00	\$ 16,000.00	\$ 16,000.00	\$ 10,000.00	\$ 10,000.00	\$ 5,327.00	\$ 5,327.00
38	Furnish, Install, Maintain and Remove Temporary Chain Link Fencing around contractor's lay down area, complete in place per Specification 701.	830	LF	\$ 15.00	\$ 12,450.00	\$ 5.00	\$ 4,150.00	\$ 6.00	\$ 4,980.00	\$ 24.00	\$ 19,920.00
39	Furnish, Install, Maintain and Remove temporary moving Chain Link Fence around any construction equipment and open trenches within cattle pen, complete in place per Specification 701.	1	LS	\$ 5,000.00	\$ 5,000.00	\$ 3,500.00	\$ 3,500.00	\$ 3,000.00	\$ 3,000.00	\$ 1,188.00	\$ 1,188.00
40	Furnish, Install, Maintain and Remove Concrete Washout, complete in place per Drawing 00G-03.	1	EA	\$ 1,000.00	\$ 1,000.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 4,397.00	\$ 4,397.00
41	Furnish, Install, Maintain and Remove Stabilized Construction Access as shown on the plans, complete in place per Specification 641.	2	EA	\$ 2,500.00	\$ 5,000.00	\$ 1,200.00	\$ 2,400.00	\$ 1,500.00	\$ 3,000.00	\$ 2,375.00	\$ 4,750.00

**City of Round Rock  
Gattis School Rd Wastewater Improvements  
Bids Opened: 11/29/18 at 2:00 pm**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount	Unit Price	Total Amount
42	Furnish and Install Filter Fabric Fence or 12" dia. Mulch Logs (staked at a maximum of 8 ft spacing per plans) including removal upon conclusion of work. Install all filter fabric or mulch logs for the site prior to any other construction, complete in place per Specification 642.	3,877	LF	\$ 3.00	\$ 11,631.00	\$ 5.00	\$ 19,385.00	\$ 4.00	\$ 15,508.00	\$ 7.00 <sup>6</sup>	\$ 27,139.00
43	Furnish, Install, Maintain and Remove Creek Crossing appurtenances per Plans, complete in place per Specification 642.	1	LS	\$ 5,000.00	\$ 5,000.00	\$ 25,000.00	\$ 25,000.00	\$ 20,000.00	\$ 20,000.00	\$ 19,934.00	\$ 19,934.00
44	Furnish, Install, Maintain, and Remove Chain Link Fence Tree Protection, complete in place per Specification 610.	34	LF	\$ 20.00	\$ 680.00	\$ 5.00	\$ 170.00	\$ 15.00	\$ 510.00	\$ 8.00	\$ 272.00
45	Furnish, Install, Maintain, and Remove Wood Slats Fence Tree Protection, complete in place per Specification 610.	11	Per Tree	\$ 750.00	\$ 8,250.00	\$ 225.00	\$ 2,475.00	\$ 200.00	\$ 2,200.00	\$ 317.00	\$ 3,487.00
46	Furnish and Install Hydromulch Seeding of disturbed areas based on 20 ft wide by 3,445 ft long plus the construction laydown area. Additional area disturbed by contractor shall be restored at his cost, complete in place per Specification 604.	2.6	AC	\$ 6,500.00	\$ 16,900.00	\$ 1,600.00	\$ 4,160.00	\$ 2,000.00	\$ 5,200.00	\$ 28,465.00	\$ 74,009.00
47	Furnish, Install, and Maintain watering and/or temporary irrigation system until revegetation is established per City specifications, complete in place per Specification 604.	2.6	AC	\$ 500.00	\$ 1,300.00	\$ 1,100.00	\$ 2,860.00	\$ 1,000.00	\$ 2,600.00	\$ 2,701.00	\$ 7,022.60
48	Furnish and Install Trench Safety System Plan, complete in place per Specification 509.	3,621	LF	\$ 2.00	\$ 7,242.00	\$ 2.00	\$ 7,242.00	\$ 15.00	\$ 54,315.00	\$ 4.00	\$ 14,484.00
49	Furnish and Install Project Sign including all Material and Labor, complete in place per Specification 802.	1	EA	\$ 850.00	\$ 850.00	\$ 750.00	\$ 750.00	\$ 3,000.00	\$ 3,000.00	\$ 2,381.00	\$ 2,381.00
50	Furnish, Install, and Maintain Traffic Control Plan and Traffic Control Devices along water and sewer line route with signage, safety barriers, and appurtenances, in accordance with plans, complete in place per Specification 803.	1	LS	\$ 25,000.00	\$ 25,000.00	\$ 125,000.00	\$ 125,000.00	\$ 15,000.00	\$ 15,000.00	\$ 2,375.00	\$ 2,375.00
51	Steel Plating or Temporary Driveway diversions to provide access to private lots during construction as necessary, complete in place per Specification 510.	6	EA	\$ 500.00	\$ 3,000.00	\$ 1,800.00	\$ 10,800.00	\$ 250.00	\$ 1,500.00	\$ 1,251.00	\$ 7,506.00
52				\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
53				\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
	<b>TOTAL AMOUNT BID No. 1</b>				<b>\$ 932,388.00</b>		<b>\$ 937,027.00</b>		<b>\$ 1,021,357.00</b>		<b>\$ 1,225,778.80</b> <sup>5</sup>

<sup>1</sup>amount on bid doc = \$627,723.00

<sup>2</sup>Statement of Bidder's Safety Experience is not signed.

<sup>3</sup>No OSHA Logs attached.

<sup>4</sup>unit price multiplied by quantity does not equal amount on bid doc

<sup>5</sup>amount on bid doc = \$1,225,848.80

<sup>6</sup>Error in quantity on Bid Form

<sup>7</sup>Written Unit Price does not match Unit Price

<sup>8</sup>amount on bid doc = \$725,853.00

<sup>9</sup>words match Amount and not Unit Price

<sup>10</sup>amount on bid doc = \$828,249.60

<sup>11</sup>Written Unit Price match Amount on all Items