

# EXHIBIT "A"




SCALE  
1" = 200'

## LEGEND:

- P.R. PLAT RECORDS OF WILLIAMSON COUNTY, TEXAS
- O.P.R. OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS
- P.O.B. POINT OF BEGINNING
- I.R.F. IRON ROD FOUND (UNLESS NOTED)
- I.R.S. IRON ROD SET

## NOTES:

1. THE PROFESSIONAL SERVICES PROVIDED HERewith INCLUDE THE PREPARATION OF A FIELD NOTE DESCRIPTION.
2. THE BEARINGS ARE BASED ON THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE CENTRAL ZONE FROM THE NORTH AMERICAN DATUM OF 1983 NAD 83 (NA2011) EPOCH 2010.00.
3. ADJOINERS SHOWN FOR INFORMATIONAL PURPOSES ONLY.




**PAPE-DAWSON ENGINEERS**

2000 SHOAL CREEK BLVD. SUITE 220 WEST AUSTIN TEXAS 78757 PHONE: 512.454.8711 FAX: 512.453.6997

TEXAS BOARD OF PROFESSIONAL ENGINEERS, FIRM REGISTRATION # 470 TEXAS BOARD OF PROFESSIONAL LAND SURVEYING, FIRM REGISTRATION # 1003801

Copyright © 2015 Pape-Dawson Engineers, Inc. All Rights Reserved.




AUGUST 3, 2015

JOB No.:

SHEET 1 OF 1

59004-15



## FIELD NOTES

### FOR

A 20.791 ACRE TRACT OF LAND BEING A PORTION THE REMNANT PORTIONS OF: A CALLED 14.206 ACRE TRACT (TRACT 3-C1), OF A CALLED 6.55 ACRE TRACT (TRACT 2-B1) OF A CALLED 1.096 ACRE TRACT (TRACT 3-C2), DEED TO HR 79 INVESTMENTS, LTD. RECORDED IN DOCUMENT NO. 2007061514 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS, SITUATED IN THE PRIOR A. HOLDER SURVEY, ABSTRACT NO. 297 IN THE CITY OF ROUND ROCK, WILLIAMSON COUNTY, TEXAS. SAID 20.791 ACRE TRACT BEING MORE FULLY DESCRIBED AS FOLLOWS, WITH BEARINGS BASED ON THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE CENTRAL ZONE FROM THE NORTH AMERICAN DATUM OF 1983 NAD 83 (NA2011) EPOCH 2010.00.

**BEGINNING** at a ½" iron rod found on a point being the northeast corner of said 14.206 acre tract, same being the northwest corner of a remnant portion of a called 24.0110 acre tract of land in deed to Church of Christ of Round Rock, recorded in Document no. 2000022099 of said Official Public Records, also being a point in the south boundary line of Lot 7 of Hidden Acre Subdivision, a subdivision according to the plat recorded in Cabinet C, Slide 226 recorded in the Plat Records of Williamson County, Texas, for the northeast corner and **POINT OF BEGINNING** hereof;

**THENCE** departing the south boundary line of said Lot 7 with the west boundary line of said 24.0110, same being the east boundary line of said 14.206 acre tract, **S 02°33'42" E** for a distance of **1511.57 feet** to a ½" iron rod found on a point in the north right-of-way line of Palm Valley Boulevard (SH 79), said point being the northeast corner of a called 0.9264 acre tract in Cause No. 07-2003-CC2 recorded in Document No. 2009014784 of said Official Public Records, said point being the southwest corner of the remnant portion of said 24.0110 acre tract, same being the southeast corner of the remnant portion of said 14.206 acre tract, for the southeast corner hereof;

**THENCE** departing the west boundary line of said 24.0110 acre tract, through, in part, the interior of said 14.206 acre tract and in part, the interior of said 1.096 acre tract, with the north boundary line of said East Palm Valley Blvd., same being the north boundary line of said 0.9264 acre tract the following three (3) courses and distances:

1. **S 77°16'57" W** for a distance of **407.92 feet** for a point of curvature hereof,

2. With the arc of a curve to the right having a radius of **11,415.16 feet**, an arc length of **73.60 feet**, a delta of **00°22'10"** and a chord which bears **S 77°27'54" W** for a distance of **73.60 feet** to a ½" iron rod for a point of non-tangency hereof, and
3. **N 56°26'39" W** for a distance of **54.92 feet** to a ½" iron rod found on a point in the west boundary line of said 1.096 acre tract, same the easterly boundary line of said 6.55 acre tract, said point being the northwest corner of said 0.9264 acre, same being the northeast corner of a called 0.15 acre tract in Cause No. 07-2003-CC2 recorded in Document No. 2007098403 of said Official Public Records, for a point of non-tangency hereof;

**THENCE** departing the west boundary line of said 1.096 acre tract, through the interior of said 6.55 acre tract, with the north boundary line of said 0.15 acre tract, the following two (2) courses and distances:

1. **N 55°23'16" W** for a distance of **20.09 feet** to a TXDOT Type II monument found, for an angle point hereof, and
2. **S 78°05'26" W** for a distance of **35.14 feet** to a ½" iron rod found on a point in the west boundary line of said 6.55 acre tract, said point being the northwest corner of said 0.15 acre tract, same being the southeast corner of a called 0.18 acre tract of land in deed to the City of Round Rock recorded in Document No. 2007062299 of said Official Public Records, for the southwest corner hereof;

**THENCE** departing the north right-of-way line of said Palm Valley Boulevard, with the west boundary line of said 6.55 acre tract, same being the east boundary line of said 0.18 acre tract, **N 08°04'29" W** for a distance of **211.12 feet** to a "Mag" nail found for an angle point hereof;

**THENCE** continuing with the west boundary line of said 6.55 acre tract, same being, in part, the east boundary lines: of said 0.18 acre tract, of a called 37.975 acre tract in deed to NEC 1460/79, Ltd, recorded in Document No. 2006040139 of said Official Public Records, a called 0.32 acre tract in deed to the City of Round Rock recorded in Document No. 2007072062 of said Official Public Records and Lot 1, Block A of Palm Valley Market Center, Section 4, Phase 1, a subdivision according to the plat recorded in Cabinet DD, Slides 302-303 of said Plat Records, **N 01°39'40" W** for a distance of **1365.79 feet** to a ½" iron rod found on a point in the south boundary line of Lot 9 of said Hidden Acres, said Point being the northeast corner of said Lot 1, same being the northwest corner of said 6.55 acre tract for the northwest corner hereof;

**THENCE** with the south boundary line of said Hidden Acres, same being the north boundary line of said 6.55 acre tract, **N 89°35'36" E** for a distance of **196.94 feet** for the northeast corner hereof;

**THENCE** with the south boundary line of said Hidden Acres, same being the north boundary line of said 14.206 acre tract, **N 89°07'31" E** for a distance of **371.24 feet** for the **POINT OF BEGINNING** and containing 20.791 acres in the City of Round Rock, Williamson County, Texas, Said tract being described in accordance with an exhibit by Pape Dawson Engineers, Inc.

PREPARED BY: Pape-Dawson Engineers, Inc.  
DATE: August 3, 2015  
JOB No.: 59004-15  
DOC.ID.: H:\survey\SURVEY15\15-59004\Exhibits\Word\20.791Ac\_Overall.docx  
TBPE Firm Registration #470  
TBPLS Firm Registration #100288-01

