

STATE OF TEXAS

COUNTY OF WILLIAMSON

#### SUPPLEMENTAL CONTRACT NO. 1 TO CONTRACT FOR ENGINEERING SERVICES

# FIRM:RODRIGUEZ TRANSPORTATION GROUP, INC.("Engineer")ADDRESS:11211 Taylor Draper Lane, Suite 100, Austin, TX78759PROJECT:Gattis School Road (Segment 3)

This Supplemental Contract No. 1 to Contract for Engineering Services is made by and between the City of Round Rock, Texas, hereinafter called the "City" and Rodriguez Transportation Group, Inc., hereinafter called the "Engineer".

**WHEREAS,** the City and Engineer executed a Contract for Engineering Services, hereinafter called the "Contract", on the 22nd day of March, 2018 for the Gattis School Road (Segment 3) Project in the amount of \$1,013,037.45; and

**WHEREAS**, it has become necessary to amend the Contract to modify the provisions for the scope of services and to increase the compensation by \$117,447.94 to a total of \$1,130,485.39;

**NOW THEREFORE**, premises considered, the City and the Engineer agree that said Contract is amended as follows:

I.

<u>Article 2, Engineering Services</u> and <u>Exhibit B, Engineering Services</u> shall be amended as set forth in the attached <u>Addendum to Exhibit B</u>. <u>Exhibit C, Work Schedule</u> shall be amended as set forth in the attached <u>Addendum to Exhibit C</u>.

II.

<u>Article 4, Compensation</u> and <u>Exhibit D</u>, Fee Schedule shall be amended by increasing by \$117,447.94 the lump sum amount payable under the Contract for a total of \$1,130,485.39, as shown by the attached <u>Addendum to Exhibit D</u>.

**IN WITNESS WHEREOF,** the City and the Engineer have executed this Supplemental Contract in duplicate.

[signature pages follow]

Supplemental Contract 0199.1770; 00415916

### **RODRIGUEZ TRANSPORTATION GROUP, INC.**

By:\_\_\_\_\_

Date

#### **CITY OF ROUND ROCK**

#### **APPROVED AS TO FORM:**

By: \_\_\_\_

Craig Morgan, Mayor

Stephan L. Sheets, City Attorney

Date

#### ADDENDUM TO EXHIBIT B Engineering Services

The additional Scope of Work to be performed by the Engineer under this Supplemental Contract is described as follows:

- Extend ROW data research and parcel preparation to the extended limits of AW Grimes.
- Extend SUE services (QL-B) to the extended limits of AW Grimes. Ten (10) additional test holes will be added.
- Extend field surveys along AW Grimes (900 LF north and 700 LF south) of previously defined limits.
- Additional Environmental Documentation Services for the inclusion of 3D visualization of the project to be presented at the property owners meeting and project open house.
- Additional Roadway Design Services to include added Plan and Profile sheets for the extended limits of AW Grimes.
- Additional Roadway Design Services to include added Plan and Profile sheets along Double Creek and the side streets within the project limits. Original sheet count assumed only intersection details would be required.
- Additional Roadway Design Services to research and coordinate the concrete pavement design at the intersections of AW Grimes and Double Creek.
- Additional Drainage Design Services to develop multiple alternatives to replace the existing culverts near the Double Creek intersections. The alternatives were developed to facilitate constructability and accommodate utilities.
- Additional Miscellaneous Design Services to include the development of additional traffic control phases at the intersections of AW Grimes and Double Creek. Original sheet count did not reflect the complexity of the reconstruction effort.

#### FC 120 – Environmental Documentation

- A. Property Owners Meeting/Public Meeting
  - 1. The Engineer shall develop 3D visualization of the proposed project improvements to be presented at the property owners meeting and project open house.

#### FC 130 - Right-of-Way Data/Utilities

- A. Right of Way Maps
  - 2. The Engineer shall obtain information on existing ROW and property information, as defined in the Contract, for the extended limits of AW Grimes.
- B. Utility Locations
  - 1. The Engineer shall gather QL-B data, as defined in the Contract, for the extended limits of AW Grimes. QL-A data, at ten (10) additional locations, will be gathered.
- C. Boundary Surveying and Parcel Preparation
  - 1. The Engineer shall perform the tasks, as defined in the Contract, for the extended limit of AW Grimes. The total number of ROW parcels for acquisition will be increased by 6 for a total of 37 parcels.

#### FC 150 – Field Surveying and Photogrammetry

- A. Field Surveying
  - 1. The Engineer shall gather design survey data, as defined in the Contract, for the extended limits of AW Grimes.
- B. Digital Planimetric Mapping (DGN) and Digital Terrain Modeling (DTM)
  - 2. The Engineer shall prepare DGN and DTM files, as defined in the Contract, for the extended limits of AW Grimes.

#### FC 160 – Roadway Design

- A. Roadway Plans
  - 1. Plan and Profile: The Engineer shall develop additional plan sheets and associated cross sections for the extended limits of AW Grimes, Double Creek and side streets (South Creek, South Crossing and Joyce Lane) within the project limits.
  - 2. Intersections: The Engineer shall research and coordinate with subject matter experts related to the concrete pavement design at the intersections of AW Grimes and Double Creek.

#### FC 161 – Drainage

- A. Culvert Layout and Detailing of Drainage Features
  - 1. Culvert Layouts: The Engineer shall develop multiple alternatives to replace the existing culverts near the Double Creek intersections. The original concept included salvaging the existing 2 7'X4' box culvert under Double Creek. The proposed culvert has been re-aligned and shifted under proposed Gattis School road to facilitate the traffic control sequence and provide room for existing and proposed utilities.

#### FC 163 – Miscellaneous

- A. Traffic Control Plan
  - 1. Traffic Control Plan: The Engineer shall develop additional details required for the construction of the AW Grimes and Double Creek intersections. The original concept included a two-phase sequence while maintaining the cross streets in the existing configuration. The proposed sequence will require a four-phase sequence at each intersection.

	Mode	Task Name	Duration	Start	Finish	Mar 18, '18   Apr 22, '18   May 27, '18   Jul 1, '18   Aug 5, '18   Sep 9, '18   Oct 14, '18   Nov 18, '18   Dec 23, '18   Jan 27, '19   Mar 3, '19   Apr 7, '19   Ma     18   2   17   2   17   1   16   1   15   30   14   29   13   28   12   27   11   26   13   28   12   27   12
- <b>v</b>		Initial Submittal (Geometric Schematic)	100 days	Sun 4/1/18	Fri 8/17/18	18 2 17 2 17 1 16 1 16 31 15 30 14 29 13 28 12 27 11 26 13 28 12 27 11 26 13 28 12 27 12
	*	Notice to Proceed	1 day	Sun 4/1/18	Sun 4/1/18	Notice to Proceed
	-5	Data Collection & Field Reconnaissance	, 15 days	Mon 4/2/18	Fri 4/20/18	Section & Field Reconnaissance
_	-5	Right of Entry Coordination	15 days	Mon 4/9/18	Fri 4/27/18	Right of Entry Coordination
	-5	Design Concept Conference (w/ DSF)	3 days	Thu 4/26/18	Mon 4/30/18	Design Concept Conference (w/ DSF)
_	-5	Initiate Project Control	5 days	Mon 4/23/18	Fri 4/27/18	Initiate Project Control
_						H&H Studies
_	÷	H & H Studies	27 days	Thu 5/3/18	Fri 6/8/18	
_		Environment Data Collection	15 days	Tue 5/1/18	Mon 5/21/18	Environment Data Collection
	-5	Geotechnical Investigation	45 days	Tue 5/1/18	Mon 7/2/18	A Geotechnical Investigation
		Survey (Design Surveys)	25 days	Mon 4/30/18	Fri 6/1/18	Survey (Design Surveys)
		Preliminary Roadway Geometry	15 days	Mon 6/4/18	Fri 6/22/18	Preliminary Roadway Geometry
	-5	Preliminary Design Cross Sections	5 days	Mon 6/18/18	Fri 6/22/18	
	-5	Preliminary Storm Drain Design	20 days	Mon 6/11/18	Fri 7/6/18	Preliminary Storm Drain Design
_	-5	Preliminary Utility Conflict Determination	5 days	Mon 7/9/18	Fri 7/13/18	Preliminary Utility Conflict Determination
	-3	Develop Sequence of Construction Layout	10 days	Mon 6/25/18	Fri 7/6/18	Develop Sequence of Construction Layout
_						Preliminary Geometric Schematic
	->	Preliminary Geometric Schematic	10 days	Mon 7/9/18	Fri 7/20/18	Initial Submittal (QAQC)
	÷	Initital Submittal (QAQC)	5 days	Mon 7/23/18	Fri 7/27/18	
_		Initial Submittal	0 days	Fri 8/3/18	Fri 8/3/18	8/3 Initial Submittal
		City of Round Rock Review Period	10 days	Mon 8/6/18	Fri 8/17/18	Gity of Round Rock Review Period
	-5	30% Submittal (Geometric Schematic/ROW Limits)	71 days	Mon 8/20/18	Mon 11/26/18	30% Submittal (Geometric Schematic/ROW Limits)
	-5	Property Owners Meeting #1	5 days	Mon 9/3/18	Fri 9/7/18	Property Owners Meeting #1
	-5	Review/Address Review Comments	, 10 days	Mon 8/20/18	Fri 8/31/18	Review/Address Review Comments
	-5	Environmental Document/Technical Reports	20 days	Fri 9/14/18	Fri 10/12/18	Environmental Document/Technical Reports
						Update Geometric Schematic/Design XS
_		Update Geometric Schematic/Design XS	10 days	Mon 9/17/18	Fri 9/28/18	Content of Construction Layout
_	->	Update Sequence of Construction Layout	5 days	Fri 10/5/18	Thu 10/11/18	
		Update Storm Drain Design	10 days	Fri 9/28/18	Thu 10/11/18	Update Storm Drain Design
		Update Drainage Report	5 days	Fri 10/12/18	Thu 10/18/18	Update Drainage Report
		Update Geotech Report	5 days	Mon 9/24/18	Fri 9/28/18	June 4 August 2 Aug
		Update Utility Conflicts	5 days	Fri 10/12/18	Thu 10/18/18	Update Utility Conflicts
	-5	Pre-Final Geometric Schematic	5 days	Fri 10/12/18	Thu 10/18/18	Pre-Final Geometric Schematic
-	-5	Public Meeting #1	, 5 days	Tue 10/23/18	Mon 10/29/18	Public Meeting #1
_	-5	30% Submittal (QAQC)	5 days	Tue 10/30/18	Mon 11/5/18	30% Submittal (QAQC)
_						11/12 30% Submittal
_	÷	30% Submittal	0 days		Mon 11/12/18	
		City of Round Rock Review Period	10 days	Tue 11/13/18	Mon 11/26/18	City of Round Rock Review Period
		60% Submittal (PS&E)	65 days	Tue 11/27/18	Mon 2/25/19	I GO% Submittal (PS&E)
	-5	Property Owners Meeting #2 (If Applicable)	5 days	Tue 12/4/18	Mon 12/10/18	Property Owners Meeting #2 (If Applicable)
	-5	Review/Address Review Comments	5 days	Tue 11/27/18	Mon 12/3/18	Review/Address Review Comments
	-5	Final Reports (Env., Drng, Geo.)	5 days	Tue 11/27/18	Mon 12/3/18	Final Reports (Env., Drng, Geo.)
-	-5	Utility Coordination Meetings	30 days	Tue 12/4/18	Mon 1/14/19	Utility Coordination Meetings
	-5					Final Geometric Schematic
_	-	Final Geometric Schematic	5 days		Mon 12/24/18	Begin 60% Detailed Design (Plan Sheets)
_		Begin 60% Detailed Design (Plan Sheets)	45 days	Tue 12/4/18	Mon 2/4/19	
	-5	Public Meeting #2 (If Applicable)	5 days	Tue 12/25/18	Mon 12/31/18	Public Meeting #2 (If Applicable)
		60 % Submittal (QAQC)	5 days	Tue 2/5/19	Mon 2/11/19	60 % Submittal (QAQC)
	-5	60% Submittal	0 days	Mon 2/11/19	Mon 2/11/19	2/11 60% Submittal
	-5	City of Round Rock Review Period	10 days	Tue 2/12/19	Mon 2/25/19	City of Round Rock Review Period
	-5	90% Submittal (PS&E)	110 days	Tue 1/1/19	Mon 6/3/19	
-	-3	A.W.Grimes Supplemental Survey and SUE	30 days	Tue 1/1/19	Mon 2/11/19	A.W.Grimes Supplemental Survey and
-		Review/Address Review Comments	5 days	Tue 2/26/19	Mon 3/4/19	
-						
-	÷	Utility Coordination Meetings	30 days	Tue 3/5/19	Mon 4/15/19	
_		Continue 90% Detailed Design (Plan Sheets)	50 days	Tue 3/5/19	Mon 5/13/19	
	÷	Supporting Documents (Estimate, GN, Construction Schedule)	15 days	Tue 4/23/19	Mon 5/13/19	
		90% Submittal (QAQC)	5 days	Tue 5/14/19	Mon 5/20/19	
	-5	90% Submittal	0 days	Mon 5/20/19	Mon 5/20/19	5/20/4
	-5	City of Round Rock Review Period	10 days	Tue 5/21/19	Mon 6/3/19	
-	-5	Final Submittal (PS&E)	40 days	Tue 6/4/19	Mon 7/29/19	
		Review/Address Review Comments	5 days	Tue 6/4/19	Mon 6/10/19	
	÷	Finalize Detailed Design (Plan Sheets)	30 days	Tue 6/11/19	Mon 7/22/19	
	÷	Finalize Supporting Documents (Estimate, GN, Construction Schedule)	5 days	Tue 7/16/19	Mon 7/22/19	
1		Final Submittal (QAQC)	5 days	Tue 7/23/19	Mon 7/29/19	
		Final Submittal	0 days	Mon 7/29/19	Mon 7/29/19	
		nenortion Group Inc	Summary		Critical	

Page 1

19 7	11	un 16, '1 26	11		Jul 21, 26	'19 10	Aug 25	25, '19 9	24	Sep 29, '' 9	24	Nov 3, 8	'19 23	Dec 8	8, '19 23	7	Jan 12, '20 22	6
_				-														
				-														
-				-														
				_														
_				_														
				_														
-				-														
				+														
_				_														
				-														
				_														
				-														
_				-														
				-														
_				_														
				-														
_				_														
				-														
9	0% Sı	ıbmitt	al (P	5&I	E)													
n N	leetin	as																
		ys etaile	d Des	ign	) (Pla	n She	ets)											
							onstru	ction	Sched	ule)								
<b>S</b> 17	hmitt	al (QA	00															
	ıbmitt			+														
Ci	ty of	Round	Roc															
Ē.	Devi		Idroc				omitta		E)									
4		ew/AC					ments ailed D		(Plan	Sheet	s)							
												GN, Co	onstru	ction S	Schedu	ule)		
			6		E)	al 602	m:4+-'	(0.4.0	0									
			9 7/2				mittal omitta		<b>-</b> )									
		I		<u> </u>						1						<u> </u>		

## Addendum to Exhibit D Fee Schedule

RODRIGUEZ TRANSPORTATION GROUP, Inc. Estimate of Engineering Services Budget			City of Round Rock Gattis School Road (Segment 3)						
TASK	RODRIGUEZ TRANSPORTATION GROUP, INC.	CORSAIR CONSULTING LLC	COX McLAIN ENV. CONSULTING INC.	HDR ENGINEERING INC.	INLAND GEODETICS LLC	K FRIESE & ASSOCIATES INC.	NANCY LEDBETTER & ASSOCIATES INC.	TOTAL COST	
FC 110 Route and Design Studies; Geotechnical Investigation	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	
FC 120 Environmental Documentation	\$5,665.60	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$5,665.60	
FC 130 ROW Data/Utilities	\$4,487.28	\$0.00	\$0.00	\$0.00	\$26,108.00	\$0.00	\$0.00	\$30,595.28	
FC 140 Project Management and Administration	\$0.00	\$0.00	\$0.00	\$0.00	\$1,256.00	\$0.00	\$0.00	\$1,256.00	
FC 150 Field Surveying and Photogrammetry	\$0.00	\$0.00	\$0.00	\$0.00	\$10,866.00	\$0.00	\$0.00	\$10,866.00	
FC 160 Roadway Design	\$24,997.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$24,997.00	
FC 161 Drainage	\$9,189.82	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$9,189.82	
FC 162 Signing, Pavement Markings, Signals and Illumination	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	
FC 163 Miscellaneous	\$8,674.24	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$8,674.24	
Subtotal - Labor	\$ 53,013.94	\$-	\$-	\$-	\$ 38,230.00	\$	\$-	\$ 91,243.94	
Subtotal - Other Direct Expenses	\$ 25,628.00	\$-	\$-	\$-	\$ 576.00	\$-	\$-	\$26,204.00	
GRAND TOTAL	\$ 78,641.94	\$-	\$-	\$-	\$ 38,806.00	\$-	\$-	\$ 117,447.94	