



City of Round Rock
221 E. Main St.
Round Rock, TX. 78664

September 30, 2019

Attn: Brandon Pritchett

Ref: Floway Pump Quote- REVISED

1- Floway Model 18MKL/N 3stage vertical turbine pump. Pump to include cast iron/bronze fitted bowl assembly, 12" flanged discharge column, stainless steel line shafting, 14" fabricated steel discharge head with a packed stuffing box. Pump to be a duplicate of S/N 22739-5.

LOT NET TOTAL WITH FREIGHT INCLUDED TO JOBSTIE.....\$ 65,500.00

1- Motor, 450HP, 1800RPM, 3phs, 460V, vertical solid shaft, high thrust, WP-1 enclosure, Frame 5008VPH, premium efficient, 175% extra high thrust, VPI-2000 insulation system, inverter duty rated, with thermostats, insulated upper bearing, grounding ring and non-reverse ratchet.

Note: Motor to be current design.

LOT NET TOTAL WITH FREIGHT INCLUDED TO JOBSTIE.....\$ 37,750.00

Shipment:

Pump: 18-20 weeks after order.

Motor: 12-14 weeks after order.

Please let me know if you have any questions or need any additional information.

Prepared by,

Randy Key

DXP Enterprises, Inc.
1510 W. Shady Grove, Grand Prairie, TX, 75050 (972) 441-5500 fax (866) 916-1905



Celebrating a Century of Pioneering Solutions in Industrial Distribution

